PRODUCT SPECIFICATIONS



1441 BROADWAY 28TH FLOOR

NEW YORK CITY T 212.675.0030 NY 10018

F 212.675.8175

CARVART.COM

SECTION 10 22 43 STACKING GLASS WALLS/DOORS glassSTACKWALL>Motion

PART1 GENERAL

1.1 SECTION INCLUDES

- A. Furnish-only (unless otherwise specified) Carvart® custom stacking dryglazed aluminum frameless/framed stacking glass walls/doors.
 - 1. Aluminum frame with structural glazing components (HPL components optional)
 - 2. Top track
 - 3. Glass (HPL Optional)
 - 4. Rolling hardware (specified per weight and panel size)
 - 5. Gaskets/brushes and drop seals
 - 6. Steel threaded rod suspension structure
 - 7. Automatic Seals Control
 - 8. Telescopic End Panel (manual operation or with automatic operator)
 - 9. Accessories as specified (not included in glassSTACKWALL spec)

1.2 RELATED REQUIREMENTS

- A. Section 06100 Rough Carpentry: Blocking and requirements for fastening wall and ceiling products.
- B. Section 092216 Non-Structural Metal Framing: Framing and blocking for metal framing.

1.3 REFERENCE STANDARDS

- A. U.S. Architectural & Transportation Barriers Compliance Board. Americans with Disabilities Act (ADA), Accessibility Guidelines for Buildings and Facilities (ADAAG), Washington, DC: GPO, 1991.
- B. ANSI Z97.1 Standard for Glazing Materials Used in Buildings Safety Performance Specifications and Methods of Test.
- C. ASTM C1036 Specification for Flat Glass.
- D. ASTM C1048-04 Specification for Heat-Treated Flat Glass Kind HS, Kind FT Coated and Uncoated Glass.
- E. ASTM C1036 Specification for Architectural Flat Glass.
- F. UNI EN ISO 10140-2 Sound Reduction Index (R)
- G. GANA (Glass Association of North America) Glazing Manual.
- H. GANA (Glass Association of North America) Glass Design Guide.

1.4 SUBMITTALS FOR INFORMATION

A. Include material descriptions, color charts, hardware information, construction and anchoring details, component fabrication, and installation requirements.

- B. Shop Drawings: Provide shop drawings indicating fabrication and installation of partition assemblies and screen attachment. Include layout plan, elevations, construction sections, panel details, and required attachment to adjacent construction.
- C. Samples: Submit 4" x 4" glass square samples of material and thickness specified for each color and finish indicated.
- D. Maintenance Kit: Provide manufacturer's standard maintenance kit, including special tools for adjusting hardware.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: Engage an experienced installer who has been trained to install cubicle systems similar in design and extent to those indicated for this Project and who is acceptable to the cubicle system manufacturer.
- B. Source Limitations: Obtain cubicle systems and screens from a single manufacturer with resources to provide materials of consistent quality in appearance and physical properties without delaying the Work.
- C. Perform Work in accordance with [GANA Glazing Manual,] [GANA Sealant Manual,] [and] [GANA Laminators Glass Design Guide] for glazing installation methods. [Maintain [one (1)] [____] copy on site.] . Installer Qualifications: Company specializing in performing the work of this section [with minimum [_____] years [documented] experience,] [approved by Carvart®].

1.6 DELIVERY, STORAGE & FIELD CONDITIONS

- A. Deliver materials to Project site in undamaged condition.
- B. Store and handle cubicle system components and related materials to prevent deterioration or damage due to moisture, temperature changes, contaminants, corrosion, breakage, chipping, or other causes.
- C. Field Measurements: GC/client to verify dimensions in areas of installation by field measurements before fabrication and indicate measurements on Shop Drawings. Field dimensions to be communicated to Carvart PM by date indicated on schedule and providing VIF-indicated dimensions on shop. Hold dimensions are responsibility of GC/client. Coordinate fabrication schedule with construction progress to avoid delaying the installation schedule.

1.7 WARRANTY

- A. glassSTACKWALL Warranty: Submit a written limited warranty executed by the manufacturer stating that the glassSTACKWALL>Motion system is free from defects in materials and workmanship and agree to replace cubicle system and screen components that do not retain their original qualities within the specified warranty period.
 - a. Warranty Period: One (1) year from date of Substantial Completion.

PART 2 PRODUCTS

1441 BROADWAY 28TH FLOOR NEW YORK CITY NY 10018 T 212.675.0030 F 212.675.8175

CARVART.COM

2.1 OWNER-FURNISHED PRODUCTS

A. All structural components above top track (unless steel structure furnished by Carvart® is specified) are to be supplied and coordinated and installed by owner/client/GC and structural consultants. Carvart to furnish glassSTACKWALL hardware and glass only (optional HPL).

2.2 MANUFACTURERS

- A. Acceptable Manufacturer: Carvart 1441 Broadway, New York, NY 10018; Email <u>info@carvart.com</u>; Website <u>www.carvart.com</u>; Phone (212) 675-0030.
- B. Substitutions: Not permitted. Requests for substitutions will be considered in accordance with provisions of Section 01600.

2.3 MATERIALS – GLASS

- A. Glass: 3/8" -9/16" laminated or monolithic glass, tempered as required.
 - 1. Material Thickness: 3/8" 9/16" nominal.
 - 2. Color and Pattern: To be selected by the Architect from manufacturer's standard selections. Custom colors available upon request and within manufacturers fabrication limitations.

2.4 MATERIALS - HARDWARE

- A. Manufacturer's standard design, heavy-duty operating hardware.
- B. Semi-Automatic drop seals (top and bottom)
- C. Fasteners and Anchors: not furnished by Carvart®
- D. Trolley hardware: supplied and determined by manufacturer
- E. Top track: cut to size and includes maintenance piece
- F. Electrical components operating semi-automatic seals
 - a. Option: Hand Operated Expanding Telescopic panel Includes Hand Crank

2.5 MATERIALS - HARDWARE FINISH

- A. Aluminum finish:
 - a. Anodized finish in various options per manufacturer
 - b. Any RAL powder coated option

2.6 MATERIALS - HIGH PRESSURE LAMINATE

- A. HPL panels with MDF core available on request
- B. Finishes:
 - a. Solid color, metallic, fabric, writable surface, pattern

2.7 OPERATION

A. CARVART motorized seals: individual panels that are manually operated by hand (top hung) with electrically operated vertical seals and top/bottom drop seals

PART 3 EXECUTION

3.1 EXAMINATION

A. Carvart is not responsible for installation. Receiver responsible for taking delivery must report any missing or damaged material within 48 hours of delivery to validate any claims. Any materials that are damaged or missing that are identified after the 48 hours will be the responsibility of the receiver/client.

3.2 PREPARATION

A. Field conditions must be prepared per the approved shop drawings. All blocking must be located and to the spec on the shop drawings.

3.3 INSTALLATION

- A. Install top track and door panels in accordance with manufacturer's written installation instructions.
- B. Assemble panels according to individual panel assembly instructions

3.4 CLEANING

- A. Section 01700: Cleaning installed work.
- B. Remove glazing materials from finish surfaces.
- C. Remove labels after Work is complete.
- D. Clean glass and adjacent surfaces.
- E. To maintain aesthetics, it is important to clean the glass during and after construction. For routine cleaning, use a soft, clean, grit-free cloth and a mild soap, detergent, or window cleaning solution. Rinse immediately with clean water and remove any excess water from the glass surface with a squeegee. Do not allow any metal or hard parts of the cleaning equipment to contact the glass surface. Clean cubicle components in accordance with manufacturer's instructions and recommendations.

3.5 PROTECTION OF FINISHED WORK

- A. Section 01700: Protecting installed work.
- B. Protect installed glass from damage during construction.
- C. Protect installed glass from contact with contaminating substances resulting from construction operations.
- D. Touch-up, repair or replace damaged products before Substantial Completion. Remove and replace glass that is broken, chipped, cracked, abraded, or damaged in other ways during construction period, including natural causes, accidents, and vandalism.